

Section 10 Dust Control

Section 10 Dust Control

4-1001 General

Under the terms of the project contract, the contractor must control dust. The contractor must maintain such control whether payment is included in the prices paid for the various items of work involved or whether payment is made separately.

4-1001 General

4-1002 Before Work Begins

During this preliminary inspection, take the following steps:

- Determine whether a planned method to control dust is included in the contractor's approved water pollution control plan.
- Whenever it is proposed to handle temporary traffic changes on an unpaved roadway, anticipate the necessity for dust control. See Section 4-17, "Watering," and Section 4-18, "Dust Palliative," in this *Construction Manual* for additional factors relating to dust control.

4-1002 Before Work Begins

4-1003 During the Course of Work

Notify and require corrective action whenever the contractor is not adequately controlling dust. In cases of neglect, work may be suspended under the resident engineer's authority, pursuant to Section 8-1.05, "Temporary Suspension of Work," of the *Standard Specifications*.

4-1003 During the Course of Work

4-1004 Measurement and Payment

Pay for dust control as extra work only when public traffic has caused dust. In all other cases dust control is included in the various items of work involved.

4-1004 Measurement and Payment