

Section 11 Mobilization

Section 11 Mobilization

4-1101 General

Section 11-1.01 “Description,” of the *Standard Specifications*, describes the work to be included in the lump sum contract item for mobilization.

4-1101 General

4-1102 Before Work Begins

The resident engineer does not need to do any preparatory work for the mobilization contract item.

4-1102 Before Work Begins

4-1103 During the Course of Work

Separate work chargeable to mobilization from other contract item work on daily reports. Exclude the cost of work covered under the mobilization contract item from contract item costs when making adjustments in accordance with Section 4-1.03, “Changes,” of the *Standard Specifications*. The contract item for mobilization includes:

4-1103 During the Course of Work

- Setting up the contractor’s field offices, equipment yards, security fencing, and on-site materials processing plants.
- Grading access roads to offices, plants, and equipment yards.
- Acquiring utility services.
- Moving personnel, equipment, and supplies to the job site.

The contract item for mobilization does not include:

- Delivering materials to the job site. This work is paid for by the applicable contract item.
- Developing a water supply for contract work. See Section 17, “Watering,” of the *Standard Specifications*.
- Furnishing and erecting signs. See Section 12-3.06, “Construction Area Signs,” of the *Standard Specifications*.
- Grading for access to excavation areas. This work is normally covered under the roadway excavation contract item.
- Moving equipment and temporary structures off the site and removing excess material. See Section 4-1.02, “Final Cleaning Up,” of the *Standard Specifications*.

4-1104 Measurement and Payment

The Contract Administration System (CAS) automatically makes progress payments for the mobilization contract item.

4-1104 Measurement and Payment